

VERMAUERUNGSHINWEISE:

- SILRATH AK60 UND SUPRATH A40-I -STEINE VERLEGT MIT MÖRTEL M60, PORRATH FL24-10 UND PORRATH 800 -STEINE VERLEGT MIT MÖRTEL C30-4b, ALLE MÖRTELFUGEN MAXIMAL 2mm,
- VERARBEITUNGSHINWEISE FÜR MÖRTEL UND CARATH-MASSEN SIND AUF DEN SÄCKEN ANGEGEBEN BZW. AUS BEILIEGENDER DOKUMENTATION ERSICHTLICH,
- CAS UND FL-STEINE IM BEREICH VON FF-BETON MIT ÖLPAPIER ABDECKEN,
- VOR DEM ANSCHWEISSEN HALTEBEIN HE1-..., IN KALTBITUMEN TAUCHEN,
- HALTEEBEN MIT ELEKTRODEN BÖHLER FOX A7-A ANSCHWEISSEN,
- ALLE BLECHTEILE UND ROHRSTUTZEN IM BEREICH VON FF-BETON MIT ½" - KERAMIKFASERMATTE UMWICKELN.

$t_{max} = 1000°C$

DIESE ZEICHNUNG BEFINDET SICH IM UNSER EIGENTUM BESCHÄFTIGT. DIE SIE WEDER VERVIELFÄLTIGEN NOCH DRITTEN ZUGÄNGLICH MACHEN DÜRFEN, SOWIE SIE NICHT FÜR DEN ANGEBOTENEN ZWECK VERWENDEN UND NICHT NACHGEBILDET WERDEN DÜRFEN OHNE UNSERE SCHRIFTLICHE ERMÄCHTIGUNG.

THE CONTENT OF THIS DRAWING IS OUR INTELLECTUAL PROPERTY. THIS DRAWING IS SUBJECT TO THE RECEIVER ONLY FOR HIS OWN PURPOSE. THIS DRAWING MAY NOT BE COPIED OR DISTRIBUTED TO THIRD PARTIES WITHOUT OUR WRITTEN PERMISSION AND MAY NOT BE USED FOR ANY OTHER PURPOSE.

	Datum Date	Name Name	Änderung Modification	Zeichnungsnummer Drawing number	Datum Date	Name Name
Gezeichnet Drawn	10.07.2003	RG	1:15	RW03.0646/01-0		
Geprüft Checked						

MAWERA

FEUERUNG 3300 kW

Proj.:35.86.00.2000.01 / Hydr. Einschub AUSMAUERUNG

RATH AUTOCAD 2003